Standard Operating Procedure: Tower Crane Pre-Operation Inspection

Document Number: SOP-CRANE-004 (Dummy/Fictional content — for demo purposes only)

1. Purpose

This fictional procedure describes the daily pre-operation inspection checklist for tower cranes at a construction site, used here purely as sample content for a document search demo.

2. Inspection Checklist

- Check wire rope for fraying, kinks, or broken strands before each shift.
- Verify load moment indicator (LMI) is calibrated and functioning.
- Inspect hook and safety latch for deformation or cracks.
- Confirm anti-collision system is active when multiple cranes operate on site.
- Test emergency stop button and verify audible alarm response.
- Maximum wind speed for safe lifting operations is 45 km/h; operations must halt above this threshold.

3. Responsible Party

The designated crane operator and site safety officer must both sign off on the inspection checklist before any lift begins. Non-compliance requires immediate escalation to the Project Engineering Manager.